	...ing capacitor type ceiling fan complete with down rod blades, shackle, ...ge etc., for operation on 230 volts, 50 cycles. Single phase AC supply ...ming to IS 374-1979 and with double ball bearing system. (Page No - ... Item No 7.3.1 Electrical PWD SR 2019-20) —— All terms and conditions are ... tender document	Each	0.00	2100.00	Rupees Two Thousand One Hundred Only
	...plying ...litres capacity vertical/horizontal type wall mounting Electrical ...water heater with 22 SWG copper/SS sheet metal inner Container tinned ...side and anticorrosive paint outside and 20 SWG MS sheet metal outer	Each	0.00	2100.00	Rupees Two Thousand One Hundred Only
133	Supplying of ....feet - PVC Batten with integrated LED tube ....W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50/60Hz & Power factor >0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition. Page No -64, Item No 12.3.2, Electrical PWD SR 2019-20) —— All terms and conditions are as per tender document	Each	0.00	375.00	Rupees Three Hundred Seventy Five Only
134	Supply of round/square recess/surface mounted rolling type LED Down light with ....W GU 10 LED Lamp Rib Fabricated from Die cast aluminium with white powder coated prewired to mains connector & has swiveling unit of aluminium die cast eye ball & LED Lamp position retained by circular wire spring, with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50/60Hz & Power factor >0.9 along with CE approved. 2years Warranty against any manufacturing defect working under standard electrical condition (Page No -64, Item No 12.5.1 Electrical PWD SR	Each	0.00	500.00	Rupees Five Hundred Only
135	Supplying and fixing one of 230 volts Ding dong bell and a flush type bell push with gang box fixed on necessary wooden or rawl plugs using NF screws with Remote (Page No -71, Item No 13.2.1 Electrical PWD SR 2019-20) —— All terms and conditions are as per tender document	Each	0.00	220.00	Rupees Two Hundred Twenty Only
136	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 12	No	0.00	2999.00	Rupees Two Thousand Nine Hundred Ninety Nine Only
137	Supply & fixing o(children multi play equipment with spiral slide, monkey bar with number pannel . Upright structural posts of height 4.2 m are to be hot dip galvanized steel with a 114 mm OD and 2.2mm wall thickness of tubing . Roof of size 1.9m x 1.7m x 0.77 m , spiral slide of size2.56m x 1.85m x 2.68m. Top rails of monkey bar size 1.8m x 1.3m are all robotic welded & fabricated from 48mm OD galvanized steel pipes for theouter bars &32 mm OD galvanized steel for the inner parallel bars with 6 baked on powder coated finish. Oeck of size 1.45 x 1.45 m are pressed and punched , welded ,sand blasted ,powder coated to 2.2mm thickness or vinyl coated to a thickness of 4mm . Deck of size 1.45 x T.45 m are pressed and punched , welded ,sand blasted,powdei coated to 2.2mmthickness or vinyl coated to a thickness of 4mm. Deck, step, platform ,stairs, baffle shall be all robotic welded. Inclined ramps of size 1.92m x 0.65m , stair case of size 1.km x 0.77m are fabricated from solid 2mm perforated solid punched steel Frisbee climber , piped walls of	Each	1.25	1567110.00	Rupees Fifteen Lakh(s) Sixty Seven Thousand One Hundred Ten Only
	Above 125%	Each	0.75	1567110.00	Rupees Fifteen Lakh(s) Sixty Seven Thousand One Hundred Ten Only
138	Supply and fixing of childern Multi Play Equipment with double owing, curved side toddler slide with animated roof Upright structural posts of height 2.7 m and 3 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. The poles are welled on to a base plate made from steel with 114mm inner diameter. Deck of size 1.4'i x 1.45m and Staircase of size 1.48 m x 0.60 m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre hunched for attachments. Handrail of height 1.90 m and Dia 32 mm shall be an ali-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Exposed hardware shall be covered with ultra violet stabilized plastic safety caps as per Sun Roof of size 2.0 m x 1.78 m x 0.77m, Spiral Slide of size 2220 mm x 1630 mm x 1880 mm , Straight Slide of size 1645 mm x 800 mm x 1140 mm, Panels. Roofs and panels are copyrighted and IP protected worldwide. Spring Climber of thickness Dia 38 mm, 3 step ladder , Frisbee Climber ,Piped walls of Height 2.7 m are all robotic welded fabricated from 32 O.D. galvanized steel pipes for the outer pipes and 25mm O.D. galvanized steel for the inner parallel bars with a baked on powder coat finish. The rates are \o be inclusive of supply and installation at site.	Each	0.00	997000.00	Rupees Nine Lakh(s) Ninety Seven Thousand Only

Scanned with CamScann

	...and fixing of childern Adventure Play Equipment Upright structural ...d height 2.00 m , and 2.60 m are to be schedule HOT DIP Galvanized ...ith a 114mm OD and 2.2mm (wall) thickness of the tubing. The Rock ...limber clamped to the poles is of size 1655 mm x 1148 mm x 2410 mm in ...which the climbing pegs are connected in a PE board is of size 150 mm x 109 ...mm x 74 mm.This PE board is connected to two galvanized steel rods of size ...Dia 48 mm. The triangle shaped Zig Zag jumper which is of size 1200 mm x 90 ...mm x 33 mm is made of Virgin LLDPE and connected between the poles and ...galvanized steel rods of the rork climber.The triangle shaped Fin climbers ...which is made of PE and 3 holed plastic climber which is made of Virgin LLDPE ...are fixed in galvanized steel rods is of size Dia 48 mm. These climbers are fixed ...between the 3 poles with 2 top rails which is made of galvanized steel is of size ...Dia 60 mm. The net jumper is of size Dia 1100 mm is connected to the poles ...with 2 curved rods of size Dia 60 mm and is made of galvanized steel.The rates ...ar0 to be inclusive of supply and Installation at site. Inclusive of All Taxes and Transportation Chages —— All terms and conditions are as per tender document	Each	0.00	940000.00	Rupees Nine Lakh(s) Forty Thousand Only
140	Supply and fixing of cfiildern Play Equipment Fiero A Swing : Shaped structural posts of height 2.31 m are to be schedule HOW DIP Galvanized steel with a 114mm OD and 2.3mm (wall) thickness of the tubing. Plastic Components such as swing seats [superthick plasticj shall be animated and shall be rotationally molded from antistatic, copolymer, virgin linear low density UV stabilized polyethylene, with color molded in and minimum thickness of 6 - 8mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges —— All terms and conditions are as per tender document	Each	2.50	100000.00	Rupees One Lakh(s) Only
	Above 125%	Each	0.50	100000.00	Rupees One Lakh(s) Only
141	Supply and fixing of childern Play Equipment Four Seater Seesaw : SPECIFICATIONS The See Saw consists of 2 poles of Dia 114mm and thickness of 2.5mm which balances the horizontal rod at the center which is of size 3110 mm length and Dia 114 mm. It consists of 4 seats which is made of LLDPE virgin plastic of size 305mm X 213 mm X 125 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges —— All terms and conditions are as per tender document	Each	1.25	87700.00	Rupees Eighty Seven Thousand Seven Hundred Only
	Above 125%	Each	1.75	87700.00	Rupees Eighty Seven Thousand Seven Hundred Only
142	Supply and fixing of childern Play Equipment Merry go round - DX : The Merry go round consists of a round platform which is made of galvanized steel and has a thickness of 2.5 mm. It is also power coated with the thickness of 2.5 mm. It is of Dia 1210 mm. It has 3 inverted "L" shaped handrails which is made of Galvanized steel 20 and of dimensions as 474 mmx 81a mm. It has thickness of Dia 32 mm. The 3 handrails are separated exactly. All the 3 handrails are connected to the Centre with the help of a rod which is also made of Galvanized steel and of Oia 48 mm and height 815 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges ---- All terms and conditions are as per tender document	Each	0.00	69630.00	Rupees Sixty Nine Thousand Six Hundred Thirty Only
143	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil.NO.KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All	Cum	0.00	322.00	Rupees Three Hundred Twenty Two Only
144	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 OPC cement @ 180 Kgs with 40mm and down size graded granite metal of coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	5505.00	Rupees Five Thousand Five Hundred Five Only
145	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13-cement morter 1:6 (Page no-25, Item No-5.6 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	4960.00	Rupees Four Thousand Nine Hundred Sixty Only

Scanned with CamScann

	5.3.3 Providing and constructing granite / trap / basalt size stone in basement with cement mortar 1:6,edges of stones chisle dressed not less than 15 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.3.13 (Page no-25, Item No-5.9 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	5920.00	Rupees Five Thousand Nine Hundred Twenty Only
	KSRB 4.2.2 Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with superplastiniser @ 3 Liters conforming to IS 9103:1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation for footing ,pedastals,retaining walls,return walls, walls (any thickness) including attached pilasters, columnspillars,post struts, buttresses, bed blocks, anchor blocks & Plinths etc., including cost of all materials, labour, HOM curing complete as per Specifications Specification No. KBS 4.1, 4.6(Page no-14, Item No-4.11 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	6100.00	Rupees Six Thousand One Hundred Only
148	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1) : 2005 and constructed with CM 1: 4,as per IS 2572:2005 including cost of all materials labour Charges ,Scaffolding,curing,hire charges of all materials labour charges, scaffolding,curing,hire charges of machineries etc.,complete as per specifications.KBS No. 5.4 - with solid concrete blocks of size 400X150X200 (Page no-27, Item No-5.26.2 of PWD SR 2018-19.) ---- All terms and conditions	Sqm	0.00	990.00	Rupees Nine Hundred Ninety Only
149	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page no-16, Item No-4.31 of PWD SR 2018-19.) ----	Sqm	0.00	385.00	Rupees Three Hundred Eighty Five Only
150	KSRB : 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification. Specification No. KBS 2.9 (Page no-7, Item No-2.10 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	215.00	Rupees Two Hundred Fifteen Only
151	KSRB 15-3 : Providing 18mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications -Cement Morter 1:6 (Page no-116, Item No-15.17 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	264.00	Rupees Two Hundred Sixty Four Only
152	KSRB 15.1.2 Providing flush pointing 20mm deep to square rubble, course or uncoursed stone masonry with cement mortar after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.cement morter 1:4 (Page no-115, Item No-15.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	151.00	Rupees One Hundred Fifty One Only
153	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications-With Primer (Page no-120, Item No-15.53.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	110.00	Rupees One Hundred Ten Only
4	KSRB 2.6 : Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications.specification. No. KBS 2.10.2 (Page no-7, Item No-2.13 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	2220.00	Rupees Two Thousand Two Hundred Twenty Only

Scanned with CamScann

	... and fixing stainless steel staircase railing as per Chief Architect's ... 11500/ 1983, with hand rail 50mm dia 16 gauge hollow pipe, ... vertical hollow 50mm dia pipe of 16 gauge, stainless steel vertical ... spaced at 1.20m regular intervals, and 3 Nos of 25mm dia stainless steel ... horizontal pipe are welded to vertical 50mm dia hollow pipe. The ... assembly is fixed to staircase concrete by using expansion bolts by ... drilling concrete etc., complete including cost of materials, labour, HOM of ... machines and electrical charges, etc., complete as per specifications. (Page ... no 44, item No 9.38 of PWD SR 2018-19.) ---- All terms and conditions are as	Sqm	8.00	8500.00	Rupees Six Thousand Five Hundred Only
156	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil NO.KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All	Cum	0.00	300.00	Rupees Three Hundred Only
157	KSRB 4-2.2: Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3 Liters conforming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation for footing ,pedastals,retaining walls,return walls, walls (any thickness) including attached pilasters, columnspillars,post struts, buttresses, bed blocks, anchor blocks & Plinths etc., including cost of all materials, labour, HOM curing complete as per Specifications Specification No. KBS 4.1, 4.6(Page no-14, Item No-4.11 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	6100.00	Rupees Six Thousand One Hundred Only
158	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil NO.KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All	Cum	0.00	322.00	Rupees Three Hundred Twenty Two Only
159	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 OPC cement @ 180 Kgs with 40mm and down size graded granite metal of coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	5509.00	Rupees Five Thousand Five Hundred Nine Only
160	KSRB 4-2.2: Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3 Liters conforming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation for footing ,pedastals,retaining walls,return walls, walls (any thickness) including attached pilasters, columnspillars,post struts, buttresses, bed blocks, anchor blocks & Plinths etc., including cost of all materials, labour, HOM curing complete as per	Cum	0.00	6100.00	Rupees Six Thousand One Hundred Only
161	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (Page no-16, Item No-4.28 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	278.00	Rupees Two Hundred Seventy Eight Only
162	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for columns, pillars, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per Specifications. Specification No. KBS 4.6.2 (Page no-16, Item No-4.32 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	sqm	0.00	490.00	Rupees Four Hundred Ninety Only
163	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13-cement morter 1:6 (Page no-25, Item No-5.6 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	4960.00	Rupees Four Thousand Nine Hundred Sixty Only
64	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6,edges of stones chistle dressed in courses not less than 15 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (Page no-25, Item No-5.9 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	5920.00	Rupees Five Thousand Nine Hundred Twenty Only

Sincerely

Scanned with CamScanner

	... Providing and laying in position plain cement concrete of min ... (1:5:10) @ 240kgs, with 20mm and down size graded granite metal ... aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine ... concrete laid in layers not exceeding 15 cms. thick, well compacted, in ... plinth and cills, including cost of all materials, labour, HOM curing ... as per specifications. Specification No. KBS 4.1, 4.2. (Page no-13, ... No-4.6 of PWD SR 2018-19.) ---- All terms and conditions are as per ... document	Cum	0.00	5850.00	Rupees Five Thousand Eight Hundred Fifty Only
	KSRB 5.14 : Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1) : 2005 and constructed with CM 1: 4,as per IS 2572:2005 including cost of all materials labour Charges ,Scaffolding,curing,hire charges of all materials labour charges, scaffolding,curing,hire charges of machineries etc.,complete as per specifications.KBS No. 5.4 - with solid concrete blocks of size 400X200X200 (Page no-27, Item No-5.26.1 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	sqm	0.00	985.00	Rupees Nine Hundred Eighty Five Only
167	KSRB 15-3 : Providing 18mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications -Cement Morter 1:6 (Page no-116, Item No-15.17 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	263.00	Rupees Two Hundred Sixty Three Only
168	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications-With Primer (Page no-120, Item No-15.53.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	Sqm	0.00	108.00	Rupees One Hundred Eight Only
169	KSRB 15.1.2 Providing flush pointing 20mm deep to square rubble, course or uncoursed stone masonry with cement mortar after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.cement morter 1:4 (Page no-115, Item No-15.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	150.00	Rupees One Hundred Fifty Only
170	KSRB : 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification. Specification No. KBS 2.9 (Page no-7, Item No-2.10 of PWD SR 2018-19.) ----	cum	0.00	215.00	Rupees Two Hundred Fifteen Only
171	Fabrication, supplying and erecting M.S. tubular Trusses of all spans as per approved drawing & design with prefabricated steel applications using quality material and are durable,reliable and corrosion and abrasion resistant.Welding shall confirm to latest structural welding code.Quality shall be on various parameters like shape,size,design gauge and polish.The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S pipes and welding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and	kg	0.00	118.00	Rupees One Hundred Eighteen Only
172	KSRB 8.4-1 : Providing and fixing Mangalore tile roofing using first class tiles with necessary special tiles for ridges and hips, teak wood reepers of size 50x25mm and pointed with cement mortar 1:4 over the existing rafters including cost of materials, labour, curing complete as per specifications. Specification No. KBS 8.17.-Jungle wood reepers of Size 50x25mm ---- All terms and conditions are as per tender document	Sqm	0.00	600.00	Rupees Six Hundred Only
173	Providing and fixing for flooring 20mm thick sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of including cost of all materials ,morter,labour,curing etc.,complete as per specification - minimum width of 1200mm.(Gang saw Water Cut) (Page no-112, Item No-14.61.1 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	2210.00	Rupees Two Thousand Two Hundred Ten Only

Scanned with CamScanner

	...for lowering and leveling the ground other than foundation works ...anical means up to 3.00 depth,including providing shoring strutting ...ing ,removal of stumps and other deleterious matter,dressing of sides ...ottom filling back the excavated earth to the extent required and ...ding /transporting the remaining earth upto 1.00km lead including cost of ...our & HOM as per drawing and technical Spacification.(Page no-8, Item No-...4 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	cum	0.00	65.00	Rupees Sixty Five Only
	KSRRB M100-1 Loading and Unloading of stone Boulder /Stone aggregates /Sand /Kanker /moorum. KSRRB M100-1 : Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip,complete as per specifications.Morth - 100/Chapter 1 (Page no-136, Item No-17.1 and 17.4 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	144.00	Rupees One Hundred Forty Four Only
176	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.MORTH /Chapter 3 (Page no-147, Item No-19.64 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	sqm	0.00	6.45	Rupees Six And Paise Forty Five Only
177	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No. 305 (Page no-147, Item No-19.60 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	cum	0.00	350.00	Rupees Three Hundred Fifty Only
178	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 OPC cement @ 180 Kgs with 40mm and down size graded granite metal of coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	46.96	5510.00	Rupees Five Thousand Five Hundred Ten Only
179	KSRB 14.6-2 :Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS -Heavy Duty Cobble Stones 75mm hick (P.No. 101, I.No. 14.7 of CSR 2015-16) ---- All terms	Cum	0.00	1195.00	Rupees One Thousand One Hundred Ninety Five Only
180	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. (Page no-27, Item No-5.30 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Nos	387.00	440.00	Rupees Four Hundred Forty Only
181	KSRRB M800-6. Painting two coats on New Concrete Surface:-Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces complete as per specifications. MORTH Specification No. 803 (Page no-181, Item No-24.7 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	69.72	88.00	Rupees Eighty Eight Only
182	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil.NO.KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	322.00	Rupees Three Hundred Twenty Two Only
183	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 OPC cement @ 180 Kgs with 40mm and down size graded granite metal of coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	cum	0.00	5508.00	Rupees Five Thousand Five Hundred Eight Only

Scanned with CamScanner

	...ving pre cast solid cement concrete kerb stones made out of ... with top and bottom width 114 and 165 mm respectively, 400mm ... 450mm in length finished with CM 1:3 plastering and finishing ... including formwork, curing, including cost of all materials, labour, hire ... of machinery, loading, unloading, lead and lift, transportation etc., ...plete. (Page no-27, Item No-5.30 of PWD SR 2018-19.) ---- All terms and ...itions are as per tender document	NOS	0.00	435.00	Rupees Four Hundred Thirty Five Only
	...oviding and fixing for flooring 20mm thick sadarhalli gray granite in CM 1:4 ...proportion, cut to required shape, pattern with paper joints, finished with ...cement mortar using white cement and colour pigments to match the colour ...of slab making through jointing with sealant, groves in joints including cost of ...including cost of all materials ,morter,labour,curing etc.,complete as per ...specification - minimum width of 1200mm.(Gang saw Water Cut) (Page no-112, Item No-14.61.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	2510.00	Rupees Two Thousand Five Hundred Ten Only
186	KSRRB M800-6. Painting two coats on New Concrete Surface:-Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces complete as per specifications. MORTH Specification No. 803 (Page no-181, Item No-24.7 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	88.00	Rupees Eighty Eight Only
187	Stone bench " Executive Bench : Made out of sadarohally Grey Stone with hand supports with 3Line Finishing witharch.Design with 100 mm SLAB , Fleight 90 X Length150 Width 45 Cms. ---- All terms and conditions are as per tender document	Each	21.00	18160.00	Rupees Eighteen Thousand One Hundred Sixty Only
188	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil.NO.KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	322.00	Rupees Three Hundred Twenty Two Only
189	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 OPC cement @ 180 Kgs with 40mm and down size graded granite metal of coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	5500.00	Rupees Five Thousand Five Hundred Only
190	KSRB 4-1.5: Providing and laying in position plain cement concrete of mix M 20 with OPC cement @ 300 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum, machine mixed , concrete laid in layers not exceeding 15cms thick, well compacted in foundation, plinth, and Cills including cost of all materials, labour, HOM curing complete as per Specifications Specification NO. KBS 4.1, 4.2 (Page no-13, Item No-4.5 of PWD SR 2018-19.) ---- All terms and	Cum	0.00	5750.00	Rupees Five Thousand Seven Hundred Fifty Only
191	KSRB 4-2.2: Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3 Liters conforming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation for footing ,pedastals,retaining walls,return walls, walls (any thickness) including attached pilasters, columnspillars,post struts, buttresses, bed blocks, anchor blocks & Plinths etc., including cost of all materials, labour, HOM curing complete as per Specifications Specification No. KBS 4.1, 4.6(Page no-14, Item No-4.11 of PWD	Cum	0.00	6100.00	Rupees Six Thousand One Hundred Only
92	KSRB 15-3.5: Providing 15mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.-cement morter 1:4 (Page no-115, Item No-15.13 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	225.00	Rupees Two Hundred Twenty Five Only
	KSRB 4.9.2 : Providing TMT Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the djoining members wherever necessary complete as per design (laps, hooks nd wastage shall not be measured and paid) cost of materials, labour, HOM mplete as per Specifications. Specification No. KBS 4.6.3 -TMT bars Fe 0(Page no-18, Item No-4.46.2 of PWD SR 2018-19.) ---- All terms and	Tonne	0.00	84200.00	Rupees Eighty Four Thousand Two Hundred Only

Scanned with CamScanner

	...ing Flexible Multicore Cable manufactured with electrolytic copper with low conductor conforming to IS:8130-1984 and ...ulation sheathed suitable for working voltage upto 1100Volts ...694:1990 - 2C X 1.5Sq.mm(Page no-6, Item No-2.5.1 of Electrical ...SR 2019-20.) ---- All terms and conditions are as per tender document	Mtr	0.00	40.00	Rupees Forty Only
	...and fixing of 4pole power contactor with NO/NC contacts on existing ...panel board using necessary bolts, nuts, washers and wiring etc., ...ble with AC-3 Rating and as per IS-13947- 60 to 70Amps (Page no-26, ...m No-5.13.3 of Electrical PWD SR 2019-20.) ---- All terms and conditions are ...ssing for lighting/power circuit using one of FRLS PVC insulated 1100V grade, ...multistrand copper wire with low conductor resistance single core in open or ...concealed system of wiring with specified IS-694 conforming to latest ...amendments. -16 sqmm (Page no-6, Item No-2.3.7 of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	Each	0.00	4200.00	Rupees Four Thousand Two Hundred Only
		Mtr	0.00	188.00	Rupees One Hundred Eighty Eight Only
223	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron ... and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide ... and then two coats of approved paint.- 40x40x6mm (Page no-30, Item No-S.41.1of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	Mtr	0.00	250.00	Rupees Two Hundred Fifty Only
224	Fabricating supplying and mounting MS box made out 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete - 16SWG (Page no-30, Item No-S.42.2 of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	Sqcm	0.00	0.34	Rupees And Paise Thirty Four Only
225	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. -63Amps (Page no-25, Item No-S.7.3 of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	Each	0.00	227.00	Rupees Two Hundred Twenty Seven Only
226	Supplying and fixing Microprocessor based Electronic timer (without contactor, Din Mounting using necessary bolts, nuts and washers etc.,.) 3-120sec setting. (Page no-32, Item No-S.47 of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	Each	0.00	1925.00	Rupees One Thousand Nine Hundred Twenty Five Only
227	Supplying, fixing and wiring Electronic Trivector Meter (ETV) 5 to 32/63 Amps three phase 4 wire whole current class-1 Accuracy Energy Meter.(Page no-29, Item No-S.35 of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	EACH	0.00	4740.00	Rupees Four Thousand Seven Hundred Forty Only
228	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil.NO.KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	322.00	Rupees Three Hundred Twenty Two Only
229	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 OPC cement @ 180 Kgs with 40mm and down size graded granite metal of coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	5500.00	Rupees Five Thousand Five Hundred Only
	KSRB 4-2.2: Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3 Liters conforming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms ...hick, vibrated for all works in foundation for footing ,pedastals,retaining ...alls,return walls, walls (any thickness) including attached pilasters, ...olumnspillars,post struts, buttresses, bed blocks, anchor blocks & Plinths ...c., including cost of all materials, labour, HOM curing complete as per ...ecifications Specification No. KBS 4.1, 4.6(Page no-14, Item No-4.11 of PWD	Cum	0.00	6110.00	Rupees Six Thousand One Hundred Ten Only

Scanned with CamScann

	...forming and removing centering, shuttering, strutting, ... and removal of form work for columns, pillars, post and struts, ...rectangular / polygon in plan including cost of all materials, labour ...as per Specifications. Specification No. KBS 4.6.2 (Page no-16, Item ...of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	sqm	0.00	492.00	Rupees Four Hundred Ninety Two Only
	...ising available excavated earth (excluding rock) in sides of ...excavations upto plinth in layers not exceeding 20cms in depth, comparting ...each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification. Specification No. KBS 2.9 (Page no-7, Item No-2.10 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	217.00	Rupees Two Hundred Seventeen Only
233	KSRB 4.9.2 : Providing TMT Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per Specifications. Specification No. KBS 4.6.3 -TMT bars Fe	Tonne	0.00	84150.00	Rupees Eighty Four Thousand One Hundred Fifty Only
234	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil.NO.KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	322.00	Rupees Three Hundred Twenty Two Only
235	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (Page no-7, Item No-2.11 of PWD SR 2018-19.) — All terms and conditions are as per tender document	Cum	0.00	130.00	Rupees One Hundred Thirty Only
236	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,with 200mm outer dia (Page no-77, Item No-11.56.5 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	1700.00	Rupees One Thousand Seven Hundred Only
237	KSRB 12-5.2 : Constructing brick masonry circular type manhole 1.67 m internal dia at bottom, 0.91m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diametre confirming IS :12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as	Nos	0.00	26220.00	Rupees Twenty Six Thousand Two Hundred Twenty Only
38	Earth work in EXCAVATION FOR PIPELINE TRENCHES upto 600 mm trench width by mechanical / manual means as per drawing and technical specifications, including setting out, shoring, strutting, barricading, danger lighting bracing, using sight rails & boning rodsat every 100 M wherever necessary as directed, removal of stumps\ and other deleterious matters, dressing of sides & leveling the bottom of trench to the extent required, utilizing the available excavated earth locally for the work etc. complete IN ORDINARY SOILS / ALL SOILS / HARD SOILS etc. for: (Page no-54, Item No-8.1(PIPELINE WORKS FOR WATER SUPPLY & UGD WORKS EXCAVATION), of BWS & DB SR 2017-18.) ---- All terms and conditions are as per tender document	Cum	0.00	187.00	Rupees One Hundred Eighty Seven Only
	upplying PVC ring tight pipes conforming to IS 4985:2000 with latest mendments and conveying to worksite, rolling and lowering into trenches, ying true to line and level and perfect linking at joints, testing and mmissioning, including loading unloading at both destinations and cuts of es wherever necessary including jointing of PVC pipes and specials cluding cost of specials) with jointing of approved type, with all labour with ead & lift including encasing the pipe alround to a depth of not less than 15 . with soft gravel or selected earth available from the excavation etc. plete and giving necessary hydraulic test to the required pressure as per Contractor will make his own arrangements for procuring water for	RMT	0.00	107.00	Rupees One Hundred Seven Only

Scanned with CamScanner

	earth around pipelines, in layers not exceeding 20 cms. in ing each deposited layer by ramming after watering all lead cluding cost of all labour including consolidation by mechanical approved by the Engineer in charge, when earth is at suitable moisture with desired field density upto 95% maximum dry density (modified proctor test) for restoration of roads without settlement including HOM machineries, complete. (The contractor shall take care while consolidating the earth, so that, pipes laid are not damaged due to mechanical compaction and shall restore the damaged pipes at his own cost, in case of damage) etc. with: Approved earth available nearby, lead upto 100 M and lift upto 1.5 M Note: In exceptional cases, earth may be obtained from borrow pit with extra lead, duly obtaining approval from the Chief Engineer (Page no-56, Item No-4.1(PIPELINE WORKS FOR WATER SUPPLY & UGD WORKS EXCAVATION), of	cum	0.00	103.00	Rupees One Hundred Three Only
241	KSR813-6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. (Page no-94, Item No-13.37 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Nos	0.00	1876.00	Rupees One Thousand Eight Hundred Seventy Six Only
242	KSR813-7.1-4 : Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.10 / 13.13 (Page no-95, Item No-13.55 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	Nos	0.00	1435.00	Rupees One Thousand Four Hundred Thirty Five Only
	EIRL				
E1	Providing, fabricating and fixing Special Multiplay Systems consists of FRP moulded with Aluminium chequered Platforms of size 5'X5' with 4 Support piller made out of 75mm dia G.I "B" Pipes fixed in cement concrete 1:2:4. The platforms are to be covered with tubular Slide & Mini Aquva tunnel slide made up of high quality FRP the slide is to fixed at a height of 11' and runs runs for a length of not less than 20' and the slide should be supported at regular intervals of 6' using M.S. pipes support and the platform ladder with 25mm dia MS pipes with suitable hand rails and steps made out of G I sheet with tred 4" with powder coated finish, fine quality FRP with suitable design and as per drawing Moulded FRP slides are non-corrossive, fade free,tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge ofthe with all lead and lift, loading and unloading and any incidental chatges required for	Set	1.00	593274.50	Rupees Five Lakh(s) Ninety Five Thousand Only
E2	Supply And Fixing Of Children Play Equipment Horse Rider: HDPE Of Size 0.83m X 0.31m X 0.87m Plastic Components Super Thick Plastic Shall be Rorationally Molded Anistastic Copolymer Virgin Linear Low Density UV Stabilized Polyethlyene With Colour Molded is Not Added .Spelized Connectors Such As Clamps And Couplings Are To Be Cast From Aluminium Which is Pre - treated And Curved With Baked on Powder Coat Finish.The rates Are To Be Inclusive Of Supply And Installatiion At Site Inclusive Of All	Nos	3.00	55614.25	Rupees Fifty Five Thousand Seven Hundred Seventy Six Only
E3	Supply & fixing of Pull Down Challenger (Shoulder Press) (Area - 4'6" X 3' Height 7') : All tubular steel of 2.5mm thickness are galvanized and zinc dipped. All welded joints are scalloped as necessary and welded. All welds are dressed off removing all sharp edges and burrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance - free self greased SKF ball bearings. Scope of delivery : 1 completely pre assembled equipments modules. This equipment is powder coated ---- All terms and conditions are as per tender document.	Nos	3.00	247280.80	Rupees Two Lakh(s) Forty Eight Thousand Only
E4	Supply & fixing of Seated Chest Press (Area - 4'6" X 3' Height 7') : The chest press is heavy guage steel made up of 100mm NB MS pipes. The sub structure consists of 25 mm NB MS pipes and heavy duty bushes pivoted to one end and moveable up down on the other. The seats are made up of pressed FRP, self weighted machine built to support vigorous workout for up to 2 people. The Chest press supports and promotes strength to the chest, arms, shoulders and back. The exercise can be done in repetitions by increasing the time gradually which help in building stamina. Maintenance - free self greased SKF ball bearings. The whole equipment is powder coated ---- All terms and	Nos	3.00	257251.80	Rupees Two Lakh(s) Fifty Eight Thousand Only
	Supply & fixing of Elliptical (Cross Trainer) (Area - 5' X 3', Height - 5'6") : All tubular steel of 2.5 mm thickness are galvanized and zinc dipped.All welded. All welded joints are dressed off removing all sharp edges and burrs. All metal arts are powder coated using marpol powder to the thickness of 80-20microns. Rubber: High quality grip rubber is used for the handles. Bearings aintenance-free self greased SKF ball bearings Scope of delivery: 1 mpletely pre-assembled equipment modules. This equipment is powder ted. ---- All terms and conditions are as per tender document.	Nos	3.00	147570.80	Rupees One Lakh(s) Forty Eight Thousand Only

Scanned with CamScann

	...ning of Air walker (moon walker) area-4' X 3' height 4') : This ...ment is made up of 100mm NB heavy guage pipes .The footsteps are ...ge of Aluminium castings. This helps in strengthening and toning the ... Experiment with various speeds and different levels of intensity can be ... maintenance- free self greased SKF ball bearings. This Equipment is ...owder coated. ---- All terms and conditions are as per tender document.	Nos	3.00	177483.80	Rupees One Lakh(s) Seventy Eight Thousand Only
	Supply & fixing of Doulbe health walker (Hand Puller) (Area- 5'6"x3'6" Height 6'6") : This equipment is made up of Central 100mm pillars. The first steps are made up of Aluminium castings. Two people can exercise on the equipment in a back and forth motion. Experiments with various speeds and different levels of intensity can be done. It gives cardiovascular benefits promotes strengthening the biceps,hips and lower back. Maintenance-free self greased SKF ball bearings. This Equipment is powder coated ---- All terms and conditions are as per tender document.	Nos	3.00	257251.80	Rupees Two Lakh(s) Fifty Eight Thousand Only
E8	Supply & fixing of Bicycle (Exercise Cycle) (Area- 4'x3' Height -4') : This is a stationary cycle made up of central pillar 100m pipes. The seat is made up of FRP. This equipment gives the benefits of cycling and improves blood flow to the legs. Maintenance free self-greased SKF ball bearings. The whole equipment is powder coated. ---- All terms and conditions are as per tender	Nos	3.00	139594.00	Rupees One Lakh(s) Forty Thousand Only
E9	Supply & fixing of Standing Rotation (Area- 6'x3' Height -4'6") : Providing and fixing Standing Rotation made upof 100mm NBMS pipe the sub stracture consists of 32mm NBMS pipes and heavy duty self greased SKF bearing and bushes provided to ensure smooth plate rotation, the standing plates are made up of pressed sheet metal of heavy gauge it benches in stretching the internal and external oblique's and adding emphasis on the abdominals and extensor muscles of the spine , the above equipment is duly powder coated ---- All terms and conditions are as per tender document.	Nos	3.00	147570.80	Rupees One Lakh(s) Forty Eight Thousand Only
E10	Supply & fixing of Rope Puller : The rope puller made up of 100mm NBMS pipe. The substructure consists of 32mm NBMS pipes and heavy duty pulleys provided to ensure smooth rope transition; These are primary indictor of upper body strength. The exercises phase more emphasis on the trape muscles of the back bleeps Maintenance free self greased SKF ball bearings. the above equipment is duly powder coated ---- All terms and conditions are as per tender document.	Nos	3.00	101704.20	Rupees One Lakh(s) Two Thousand Only
E11	Supply & fixing of Sitting Rotation (Area- 6'x3' Height -4'6") : This equipment is made up of 100mm NBMS pipe the sub stracture consists of 32mm NBMS pipes and heavy duty self greased SKF bearing and bushes provided to ensure smooth plate rotation, the standing plates are made up of pressed sheet metal of heavy gauge it benches in stretching the internal and external oblique's and adding emphasis on the abdominals and extensor muscles of the spine , the above equipment is duly powder coated ---- All terms and conditions are as per tender document.	Nos	3.00	133611.40	Rupees One Lakh(s) Thirty Four Thousand Only
E12	Supply & fixing of Hip Swivel (Area- 3'x3' Height -4'6") : This equipment is made up of 100mm NB central pillars. The footsteps are made up of Aluminium castings. This exercises a swinging motion on slide and thereby strengthens the ower abdomen , hips and thighs. This improves both cardiovascular fitness and flexibility. The whole equipment is duly powder coated ---- All terms and conditions are as per tender document.	Nos	3.00	197425.80	Rupees One Lakh(s) Ninety Eight Thousand Only
E13	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. ---- All terms and conditions are as per tender document.(Page no-112, Item No-14.62 of PWD SR 2018-19.	Sqm	289.62	1302.13	Rupees One Thousand Three Hundred Five And Paise Ninety Two Only
	KSRB 2.6 : Providing and filling sand in foundation to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications. specification. No KBS 2.10.2 ---- All terms and conditions are as per tender document.(Page no-123, Item No-15.74 of PWD SR 2018-19.(Page no-7, Item No-2.13 of PWD SR 2018-19.	Cum	41.31	2177.27	Rupees Two Thousand One Hundred Eighty Three And Paise Sixty Only

For

Executive Engineer,
Dasarahalli Division
BBMP Bangalore

Scanned with CamScanner